



NOTES:

1. CONDUIT LAYOUT SUPPLIED BY CONTRACTOR
2. ANCHOR BOLTS SUPPLIED AND FIELD INSTALL BY CONTRACTOR
3. ALL REBAR SHALL BE ASTM A615 GR.60
4. CONCRETE STRENGTH $f'_c = 6500$ PSI
5. CONAC 3/4" COIL INSERT C63C075312, SWL 3400 LBS, 4 PLCS

PCC

Pre-Cast Concrete Company

11400 Lang Street
Anchorage, Ak, 99515
PH (907) 348- 6730 FAX (907) 348-6734

TYPE 1A LOAD CENTER
(18" x 20" x 66")

CUSTOMER:

SENT BY: C.P.

DATE: _____

SHT. 1 OF 1